

Finance Contract:	SERBIAN INLAND WATERWAY INFRASTRUCTURE Finance Contract between the Republic of Serbia and European Investment Bank (Official Gazette of the Republic of Serbia - International Contracts No. 02/2019)
MCTI reference:	404-02-00152/1/2019-2
Type of document:	Clarification No 34 to Tender Dossier
Number of pages:	8
Number of attachments:	-
Date:	September 10, 2020

Clarification No. 34 to TD

Volume 4, Section 2.1 BoQ General

QUESTIONS	ANSWERS
Question No 1	Answer No 1
BoQ 4 It: 03-05	The geotextile is laid on the entire connection of the coarse and fine-grained material on the slop embankment facing in
"03-05 Procurement, transport and installation of water	accordance with the Construction Permit Design. Geotextile is not placed as underlay of concrete support beams.
impermeable MB 30- B6 concrete	not placed as differrally of concrete support beams.
and M150 frost resistance, in accordance with the design for the	
construction of reinforced concrete	
support beams at elevation 70.50 and 72.50 and the terminal beam at	
75.25 m.a.s.l., in accordance with	
the design. The price includes the formation and installation of	
required formwork. The price included the concrete with	
the appropriate reinforcement.	
m2 2.760,46"	
In the part of the BoQ4, which	
refers to Sections 1 and 2, Items 01- 05 and 02-05 imply the	
procurement and installation of	



geotextile. By reviewing the project documentation, we believe that in Section 3, Item 03-05 should also be refered to geotextile. Please clarify, was there a mistake in the description of the above Item?	
Question No 2	Answer No 2
Could you please provide us with more details about the position and	It is given in the Construction Permit Design - cofferdam cross section.
geometry of vibrogravel piles?	The vibro-gravel piles are placed inside cofferdam area only in alp layer; al-pm stratum that lies on it should be replaced after sheet piles are driven.
	The other location is BoQ 9.07 (44800 m) part of plateau which belongs to HBIS. There is a al-prm soil stratum covered with fill. In that zone high ore dump should lie on the concrete slab. So, only al-prm soil should be improved. Before starting construction some investigatory works should be performed to define real area and length of vibro-piles.
	Details about the position and geometry of vibro-gravel piles shall be a part of Construction design which is Contractor's obligation.
Question No 3	Answer No 3
Piles are driving in inclination of 5:1 until driving cancellation. What is alternative solution If we failed to achieve requested force?	Inclined piles which are built as a part of fixed anchor block are driving to specified length. Inclined piles for crane tracks should be driven until driving cancelation. Prior to pile driving, test piles should be driven until driving cancelation and tested. If requested force is not achieved more powerful device (hammer) has to be used. The Method statement shall be provided by the Contractor before works start.
Question No 4	Answer No 4
We need clarification for steel sheet pile driving under buttresses. Sheet piles type Larssen 25, steel	Detailed explanation is provided within the Technical documentation, Book 2/1.6 of Construction Permit Design.

Question No 5 Whether the steel sheet piling anti Anti-corrosion protection

- corrosion protection is required? Anti-co

grade S240GP.

Anti-corrosion protection is not required, only transportation protection (sheet piles shall be new).



Question No 6	Answer No 6
Can SLT be performed on test piles, because position of working piles is unfavorable for testing, so we would like to change the location?	There is no sufficient information to answer the question. According to the BoQ test piles shall be constructed nearby and tested. Some of constructed "working" piles should be tested too. The Method statement shall be provided by the Contractor before works start.
Question No 7	Answer No 7
Please, define the number of CPT and SPT tests, that is necessary to be performed after vibro compaction	It is Contructor's obligation to prove compaction results according to Serbian regulations.
Overting No. 0	

Question No 8

Please check and confirm the exact unit of measure for calculating the listed positions:

Item - 12.2 Internal building installations

Sub-schedule: ADMINISTRATIVE BUILDING - WATER SUPPLY

04-00	REINFORCEMENT WORKS			
04-01	Procurement and mechanical cutting, straightening, bending, manual placement and joining of simple and medium complex reinforcement. The norm includes: straightening with an electric straightener, mechanical cutting and bending, removal of impurities, grease and peeling rust, manual placement and joining as per the drawing, sorting and marking as per the details and local transport: manual transport of reinforcement bars onsite 20 m away.			
	Calculation per kg of completed item. Ø 4-16 mm	m ³	984,00	
05-00	MASONRY			
05-01	Installation of manhole cover			
	Calculation per m' of completed item.			
		m'	3,00	
05-02	Installation of step irons.			
	Calculation per m' of completed item.	m'	15,00	



07-00	INSULATION WORKS			
07-01	Three-layer coating of walls and manhole chamber bottom with waterproof insulation material (penetrating agent). Calculation per m² of completed item.	m'	37,50	
	Sub-schedule: BUILDING FOR SHIP CREW - WATER SUPPLY			
04-00	REINFORCEMENT WORKS			
04-01	Procurement and mechanical cutting, straightening, bending, manual placement and joining of simple and medium complex reinforcement. The norm includes: straightening with an electric straightener, mechanical cutting and bending, removal of impurities, grease and peeling rust, manual placement and joining as per the drawing, sorting and marking as per the details and local transport: manual transport of reinforcement bars onsite 20 m away.			
	Calculation per kg of completed item. Ø 4-16 mm	m ³	328,00	
05-00	MASONRY			
05-01	Installation of manhole cover Calculation per m' of completed item.			
05-02	Installation of step irons. Calculation per m' of completed item.	m'	1,00	
		m'	5,00	
07-00	INSULATION WORKS			
07-01	Three-layer coating of walls and manhole chamber bottom with waterproof insulation material (penetrating agent).			



Sub-schedule: GATEWAY CONTROL - WATER SUPPLY

No.	DESCRIPTION	UoM	QTY	UNIT PRICE (EUR)	PRICE (EUR)
04-00	REINFORCEMENT WORKS			(LOIG)	(EUI)
04-01	Procurement and mechanical cutting, straightening, bending, manual placement and joining of simple and medium complex reinforcement. The norm includes: straightening with an electric straightener, mechanical cutting and bending, removal of impurities, grease and peeling rust, manual placement and joining as per the drawing, sorting and marking as per the details and local transport: manual transport of reinforcement bars onsite 20 m away.				
	Calculation per kg of completed item.				
	Ø 4-16 mm	m ³	328,00		
05-00	MASONRY				
05-01	Installation of manhole cover				
	Calculation per m' of completed item.		1		
		m'	1,00		
05-02	Installation of step irons.				
	Calculation per m' of completed item.				
		m'	5,00		
7-00	INSULATION WORKS				
07-01	Three-layer coating of walls and manhole chamber bottom with waterproof insulation material (penetrating agent).				
	Calculation per m ² of completed item.		40.50		
		m'	12,50		



Sub-schedule: RAILTRACK GATEWAY

No.	DESCRIPTION	UoM	QTY	UNIT PRICE (EUR)	PRICE (EUR)
04-00	REINFORCEMENT WORKS			,,	
04-01	Procurement and mechanical cutting, straightening, bending, manual placement and joining of simple and medium complex reinforcement. The norm includes: straightening with an electric straightener, mechanical cutting and bending, removal of impurities, grease and peeling rust, manual placement and joining as per the drawing, sorting and marking as per the details and local transport: manual transport of reinforcement bars onsite 20 m away.				
	Calculation per kg of completed item.				
	Ø 4-16 mm	m ³	240,00		
05-00	MASONRY				
05-01	Installation of manhole cover				
	Calculation per m' of completed item.				
		m'	2,00		
05-02	Installation of step irons.				
	Calculation per m' of completed item.				
		m'	4,00		
07-00	INSULATION WORKS				
07-01	Three-layer coating of walls and manhole chamber bottom with waterproof insulation material (penetrating agent).				
	Calculation per m ² of completed item.		70.00.00.00		
		m'	18,00		



Sub-schedule: RAILTRACK GATEWAY CONTROL - SEWAGE SYSTEM

No.	DESCRIPTION	UoM	QTY	UNIT PRICE (EUR)	PRICE (EUR)
04-00	REINFORCEMENT WORKS				
04-01	Procurement and mechanical cutting, straightening, bending, manual placement and joining of simple and medium complex reinforcement. The norm includes: straightening with an electric straightener, mechanical cutting and bending, removal of impurities, grease and peeling rust, manual placement and joining as per the drawing, sorting and marking as per the details and local transport: manual transport of reinforcement bars onsite 20 m away. Calculation per kg of completed item. Ø 4-16 mm	m³			
	24-10 min	me	120,00		
5-00	MASONRY				
05-01	Installation of manhole cover				
	Calculation per m' of completed item.				
		m'	1,00		
)5-02	Installation of step irons.				
	Calculation per m' of completed item,		000232		
		m'	2,00		

Answer No 8

04-01	Procurement and mechanical cutting, straightening, bending, manual placement and joining of simple and medium complex reinforcement. The norm includes: straightening with an electric straightener, mechanical cutting and bending, removal of impurities, grease and peeling rust, manual placement and joining as per the drawing, sorting and marking as per the details and local transport: manual transport of reinforcement bars onsite 20 m away.	
	Calculation per kg of completed item.	
	Ø 4-16 mm	kg



05-01	Installation of manhole cover	
	Calculation per pcs of completed item.	pcs
05-02	Installation of step irons.	
	Calculation per pcs of completed item.	pcs
07-01	Three-layer coating of walls and manhole chamber bottom with waterproof insulation material (penetrating agent).	
	Calculation per m ² of completed item.	m2

Railtrack gateway control – Sewage system, in the recapitulation items, there are missing items for Concrete works and Reinforcement works. Those works are numbered in the tender, so please add them also in Recapitulation works.